

Addendum #1

RFP #CC612-26

BARN #2 CONCRETE

Questions and Answers:

Can water spigots on site be utilized for construction water?

- The spigots in third section are not turned on. There are plenty of other sources of water on the site.

PG9, Section 4, Notes – b, item v. Insurance, permits and inspections

What are the permits required? What inspections are required?

- No to the permits and inspections.

Will there be any QC testing performed? If so, is testing contractor supplied or CC responsibility?

- No testing

With 9-10” excavation in barn, is there any risk of shallow buried electrical or UG utilities being at risk?

- Everything should be at least 18" deep.

Excavated materials, where is the disposal area or does contractor dispose of them?

- Excavated material can be left on site and moved to a designated location.

Addition to Scope of Work:

Scope Addition: Concrete Pads Installation

The scope of work is hereby modified to include the furnishing of all labor, materials, equipment, and supervision necessary to install four (4) reinforced concrete pads, as specified below:

1. Dimensions: Each pad shall measure five feet (5') by five feet (5') in plan.
2. Thickness: Each pad shall be constructed to a uniform thickness of five inches (5').

3. Reinforcement: Reinforcement shall consist of #4 (No. 4) steel reinforcing bars placed in a grid pattern at sixteen inches (16”) on center each way.
4. Subgrade Preparation: Subgrade shall be properly prepared, leveled, and compacted to provide adequate support for the concrete pads.
5. Concrete: Concrete shall meet standard structural requirements with a minimum compressive strength appropriate for light structural use unless otherwise specified.
6. Placement and Finishing: Concrete shall be placed, consolidated, and finished in accordance with industry standards. Final finish shall be a broom finish, as appropriate for intended use.
7. Location: Final placement locations of the pads shall be as directed in the field or per project drawings, if provided.

All other terms and conditions of the original agreement shall remain unchanged.

A handwritten signature in blue ink that reads "Shane Pulliam". The signature is written in a cursive, flowing style.

Shane Pulliam
Director of Procurement

shane.pulliam@caspercollege.edu

Ph: 307-268-2633

Fax: 307-268-2880