

Addendum #1

RFP #CC619-26

RESIDENCE HALL SNOW MELT AND SIDEWALK REPLACEMENT

Notes from Job Walk and Question and answers:

- What parts of the existing snow melt system are still operational and will not be required?
 - The boilers are in good working order and the shut off valve is also in good working order. The tubing on the outside of the building under the concrete will need to be replaced. The aprons right outside the doors will not come out so the Snowmelt will remain.

- Where are the main lines for electrical and plumbing coming out into the courtyard for the snow melt system. See page #2
 - Casper College doesn't have drawing of the courtyard sprinkler system.
 - Please see page #2 for the drawing of the electrical lines in the courtyard.

- Please see ATTACHMENT 1 - 321313.00 - Concrete Paving, ATTACHMENT 2 - 321123.00 - Aggregate Base Courses, and ATTACHMENT 3 - 2024 ADA AND DRAINAGE CONCRETE. These are the specification and the engineered drawing for the concrete replacement. These drawings also include previous work that has been completed. Please only look at the drawing for the residence hall courtyard.



Shane Pulliam
Director of Procurement

shane.pulliam@caspercollege.edu

Ph: 307-268-2633

Fax: 307-268-2880

